

SCHEDULE 2

MOBILE CRANES

PART 4

CONDITIONS RELATING TO USE

Maximum length

27. The overall length of a mobile crane, together with any forward or rearward projections of any load carried on it in accordance with this Schedule, must not exceed 30 metres.