## **SCHEDULE 6**

## Rendering requirements

## Part 1

## Requirements for premises used for rendering specified risk material

- 1. The premises must be adequately separated from the public highway and other premises. Notwithstanding this, they may occupy the same site as premises where animal products which are not specified risk material are rendered provided that specified risk material is stored, handled and processed separately from other animal material and by means of equipment used only for specified risk material.
  - 2. Unauthorised persons and animals must not be permitted to have access to the premises.
- **3.** The premises or part of the premises used to process specified risk material must have a clean and an unclean section specified by the occupier, adequately separated. The unclean section must have a covered place to receive and store the specified risk material for processing and must be constructed in such a way that it is easy to clean and disinfect. Floors must be laid in such a way as to facilitate the draining of liquids. The premises must have adequate lavatories, changing rooms and washbasins for staff.
- **4.** The premises must have sufficient capacity of hot water and steam production to render specified risk material in accordance with the method in Part II of this Schedule chosen by the operator.
  - 5. The equipment used to render specified risk material must include—
    - (a) measuring equipment to check temperature and, if necessary, pressure at critical points;
    - (b) recording devices to record continuously the results of measurements; and
    - (c) an adequate safety system to prevent insufficient heating.
- **6.** To prevent recontamination of processed specified risk material by incoming specified risk material, there must be clear separation between the area of the premises where the incoming specified risk material is unloaded and rendered and the areas set aside for further processing of the heated specified risk material and the storage of finished specified risk material products.
- 7. The premises must have adequate facilities for cleaning and disinfecting the containers or receptacles in which unprocessed specified risk material is received and the vehicles in which it is transported.
- **8.** Adequate facilities must be provided for disinfecting the wheels, immediately before their departure, of vehicles transporting specified risk material or leaving the unclean section of the premises.