

SCHEDULE

Article 2

DESCRIPTION OF SCHEDULED WORKS

In the borough of Kings Lynn and West Norfolk—

Work No. 1

A barrage across the creek incorporating sluices, culverts fitted with tide flaps, moveable sections or gates, sills and a walkway commencing on the northern bank of the creek at reference point TF61542002 and terminating on the southern bank of the creek at reference point TF61552000.

Work No. 2

Strengthening works consisting of a latticed structure on the bed of the creek in the area of the creek bound by the existing dam, the barrage and the northern and southern banks of the creek.