

SCHEDULE 9

TEST PROCEDURES

PART IV

TESTS FOR PACKAGES

4. After each of the applicable tests specified in paragraphs 6 — 26 below—
 - (a) faults and damage must be identified and recorded;
 - (b) it must be determined whether the integrity of the containment system and shielding has been retained to the extent required in Schedule 8 for the package under test; and
 - (c) for packages containing fissile material, it must be determined whether the assumptions and conditions made in the assessments required by paragraphs 1 to 9 of Part XIV Schedule 8 regarding the most reactive configuration and degree of moderation of the fissile contents, of any escaped material, and for one or more packages are valid.