

SCHEDULE 3

ENGINEERING PLANT

PART 3

CONDITIONS RELATING TO USE

Maximum length

16. The overall length of engineering plant (or of any vehicle-combination permitted by this Schedule), together with any forward or rearward projections of any load carried on it in accordance with this Schedule, must not exceed 30 metres.