

## SCHEDULE

### Conditions

## PART 1

### Conditions of building operations

#### Noise limits and vibration limits

- 3.**—(1) Noise levels during construction works must not exceed 65dB (LAeq, 1hr).
- (2) Ground vibration must not exceed—
- (a) 10 millimetres per second peak particle velocity;
  - (b) 1 millimetre per second peak particle velocity on 10 or more days in any period of 15 consecutive days.
- (3) Noise and vibration limits must be measured at 1 metre from any elevation of a residential receptor.